

**LOT 1  
TURKANA NORTH & WEST**

SCHEDULE NO. 1 - PLANT AND MANDATORY SPARE PARTS SUPPLIED FROM ABROAD							
Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	CIP Unit Price <sup>1</sup>	CIP Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KAIKOR 175 kWp (175kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	175 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	175 kW (AC) Solar PV Inverters			Lot	1		
4	120 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	438 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	120 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability,			Lot	1		

	and compliance with all relevant local and international codes and standards at the time of installation.						
		<b>KAIKOR SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	612		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts, nuts, stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	612		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	35		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	431		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	487		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	34		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	300		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	16530		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	673.2		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	561		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	561		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	561		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	561		
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole (TSP/03/005-1)			No	89		
29	14M MV Concrete Pole (TSP/03/005-1)			No	5		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	94		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	4.83		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	21		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	4		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	7		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 25KVA transformer			No	4		
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	4		
<b>B5</b>	<b>Step up Transformer</b>						
37	415V/11KV 200KVA transformer			No	1		

38	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>KAIKOR SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
39	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KAIKOR SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	CIP Unit Price <sup>1</sup>	CIP Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KANAKURDIO 75 kWp (75kW AC) SOLAR PV MINIGRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	75 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	75 kW (AC) Solar PV Inverters			Lot	1		
4	60 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	188 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	60 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and			Lot	1		

	international codes and standards at the time of installation.						
		<b>KANAKURDIO SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	277		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts, nuts, stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	277		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	16		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	187		
18	LV Concrete stays - (Stay wire, stay block, stay rod)			No	172		
19	LV Concrete strut pole - (Concrete strut pole, heavy duty clamps)			No	34		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	120		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	666 0		
22	16mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	271. 2		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	226		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	226		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	226		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	226		
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole (TSP/03/005-1)			No	37		
29	14M MV Concrete Pole (TSP/03/005-1)			No	14		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	51		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	4.28		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	37		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	7		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 25KVA transformer			No	0		
36	11KV 50KVA transformer			No	2		
37	11KV 50KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	2		
<b>B5</b>	<b>Step up Transformer</b>						
38	415V/11KV 100KVA transformer			No	1		

39	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>KANAKURDIO SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
40	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KANAKURDIO SUBTOTAL C</b>					



Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	CIP Unit Price <sup>1</sup>	CIP Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KIBISH 120 kWp (120kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	120 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	120 kW (AC) Solar PV Inverters			Lot	1		
4	82 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	300 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	82 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Security equipment including CCTV cameras, IR sensors with video display at control room.			Lot	1		
11	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
12	Auxiliary power supply as per specifications			Lot	1		
13	Air conditioners for the control room as per specifications.			Lot	1		
14	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability,			Lot	1		

	and compliance with all relevant local and international codes and standards at the time of installation.						
		<b>KIBISH SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
15	10M LV Concrete Pole (TSP/03/005-1)			No	165		
16	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	165		
17	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	9		
18	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	105		
19	LV Concrete stays- (Stay wire, stay block, stay rod)			No	103		
20	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	0		
<b>B2</b>	<b>Other PDN Items</b>						
21	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	90		
22	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	6660		
23	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	270		
24	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	225		
25	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	225		
26	Ready Boards complete with mounting accessories (TSP/14/051)			No.	225		
27	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	225		

28	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
29	12M MV Concrete Pole (TSP/03/005-1)			No	0		
30	14M MV Concrete Pole (TSP/03/005-1)			No	0		
31	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	0		
32	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	0		
33	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	0		
34	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	0		
35	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
36	11KV 50KVA transformer			No	0		
37	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	0		
		<b>KIBISH SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
38	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KIBISH SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	CIP Unit Price <sup>1</sup>	CIP Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KOKURO 120kWp (120kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	120 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	120 kW (AC) Solar PV Inverters			Lot	1		
4	82 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	300 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	82 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation.			Lot	1		

		<b>KOKURO SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	137		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	137		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	7		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	91		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	96		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	26		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	60		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	738 0		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	297. 6		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	248		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	248		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	248		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	248		
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole (TSP/03/005-1)			No	23		
29	14M MV Concrete Pole (TSP/03/005-1)			No	4		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	27		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	1.82		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	13		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	3		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	3		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 50KVA transformer			No	2		
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	2		
<b>B5</b>	<b>Step up Transformer</b>						
37	415V/11KV 100KVA transformer			No	1		

38	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>KOKURO SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
39	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KOKURO SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	CIP Unit Price <sup>1</sup>	CIP Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>OROPOI 100 kWp (100 kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	100 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	100 kW (AC) Solar PV Inverters			Lot	1		
4	60 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	250 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management system			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	60 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			No.	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Lot	1		



		<b>OROPOI SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	182		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	182		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	9		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	125		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	125		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	12		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	60		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	735 0		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	296. 4		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	247		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	247		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	247		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	247			
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1			
<b>B3</b>	<b>11KV MV Distribution line</b>							
28	11M MV Concrete Pole (TSP/03/005-1)			No	0			
29	12M MV Concrete Pole (TSP/03/005-1)			No	0			
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	0			
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	0			
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	0			
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	0			
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0			
<b>B4</b>	<b>11KV Distribution Transformer</b>							
35	11KV 50KVA transformer			No	0			
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	0			
		<b>OROPOI SUBTOTAL B</b>						
<b>C</b>	<b>Mandatory spares</b>							
37	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1			
		<b>OROPOI SUBTOTAL C</b>						

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	CIP Unit Price <sup>1</sup>	CIP Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>NACHUKUI 120 kWp (120kW AC) SOLAR PV MINI-GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	120 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	120 kW (AC) Solar PV Inverters			Lot	1		
4	82 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	300 kWh Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	82 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			No.	1		
12	Air conditioners for the control room as per specifications.			No.	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation.			Lot	1		

		<b>NACHUKUI SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	177		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	177		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	13		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	158		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	158		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	17		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	30		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	636 0		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	255. 6		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	213		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	213		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	213		
26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	213		

27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole (TSP/03/005-1)			No	28		
29	14M MV Concrete Pole (TSP/03/005-1)			No	6		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	34		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	1.88		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	28		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	2		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 50KVA transformer			No	2		
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	2		
<b>B5</b>	<b>Step up Transformer</b>						
37	415V/11KV 100KVA transformer			No	1		
38	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required			Set	1		



**SCHEDULE NO. 2 - PLANT AND MANDATORY SPARE PARTS FROM WITHIN THE EMPLOYER'S COUNTRY**

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	EXW Unit Price <sup>1</sup>	EXW Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KAIKOR 175 kWp (175kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	175 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	175 kW (AC) Solar PV Inverters			Lot	1		
4	120 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	438 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	120 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation.			Lot	1		

		KAIKOR SUBTOTAL A			
<b>B</b>	<b>Power Distribution Network (PDN)</b>				
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>				
14	10M LV Concrete Pole (TSP/03/005-1)		No	612	
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)		Set	612	
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)		Km	35	
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)		No	431	
18	LV Concrete stays- (Stay wire, stay block, stay rod)		No	487	
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)		No	34	
<b>B2</b>	<b>Other PDN Items</b>				
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)		M	300	
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)		M	16530	
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)		M	673.2	
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)		No.	561	
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)		No.	561	
25	Ready Boards complete with mounting accessories (TSP/14/051)		No.	561	
26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing		No	561	
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis		Lot	1	
<b>B3</b>	<b>11KV MV Distribution line</b>				



28	12M MV Concrete Pole (TSP/03/005-1)			No	89		
29	14M MV Concrete Pole (TSP/03/005-1)			No	5		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	94		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	4.83		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	21		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	4		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	7		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 25KVA transformer			No	4		
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	4		
<b>B5</b>	<b>Step up Transformer</b>						
37	415V/11KV 200KVA transformer			No	1		
38	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>KAIKOR SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						

39	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KAIKOR SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	EXW Unit Price <sup>1</sup>	EXW Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KANAKURDIO 75 kWp (75kW AC) SOLAR PV MINIGRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	75 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	75 kW (AC) Solar PV Inverters			Lot	1		
4	60 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	188 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	60 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation.			Lot	1		

		<b>KANAKURDIO SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	277		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts, nuts, stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	277		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	16		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	187		
18	LV Concrete stays - (Stay wire, stay block, stay rod)			No	172		
19	LV Concrete strut pole - (Concrete strut pole, heavy duty clamps)			No	34		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	120		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	6660		
22	16mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	271.2		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	226		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	226		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	226		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	226		
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole (TSP/03/005-1)			No	37		
29	14M MV Concrete Pole (TSP/03/005-1)			No	14		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	51		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	4.28		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	37		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	7		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 25KVA transformer			No	0		
36	11KV 50KVA transformer			No	2		
37	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	2		
<b>B5</b>	<b>Step up Transformer</b>						
38	415V/11KV 100KVA transformer			No	1		

39	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>KANAKURDIO SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
40	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KANAKURDIO SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	EXW Unit Price <sup>1</sup>	EXW Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KIBISH 120 kWp (120kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	120 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	120 kW (AC) Solar PV Inverters			Lot	1		
4	82 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	300 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	82 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Security equipment including CCTV cameras, IR sensors with video display at control room.			Lot	1		
11	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
12	Auxiliary power supply as per specifications			Lot	1		
13	Air conditioners for the control room as per specifications.			Lot	1		
14	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and			Lot	1		

	international codes and standards at the time of installation.						
		<b>KIBISH SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
15	10M LV Concrete Pole (TSP/03/005-1)			No	165		
16	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts, nuts, s tays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	165		
17	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	9		
18	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	105		
19	LV Concrete stays- (Stay wire, stay block, stay rod)			No	103		
20	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	0		
<b>B2</b>	<b>Other PDN Items</b>						
21	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	90		
22	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	6660		
23	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	270		
24	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	225		
25	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	225		
26	Ready Boards complete with mounting accessories (TSP/14/051)			No.	225		



27	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	225		
28	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
29	12M MV Concrete Pole ( <a href="#">TSP/03/005-1</a> )			No	0		
30	14M MV Concrete Pole ( <a href="#">TSP/03/005-1</a> )			No	0		
31	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) ( <a href="#">TSP/06/035</a> ), ( <a href="#">TSP/03/021</a> ), ( <a href="#">TSP/03/003</a> ), ( <a href="#">TSP/02/004</a> ), ( <a href="#">TSP/02/003-1</a> ), ( <a href="#">TSP/04/011</a> ), ( <a href="#">TSP/02/003-2</a> ), ( <a href="#">TSP/02/002</a> ), ( <a href="#">TSP/06/036-1</a> ), ( <a href="#">TSP/07/001</a> ), ( <a href="#">TSP/03/022</a> )			Set	0		
32	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line ( <a href="#">TSP/06/020-2</a> )			Km	0		
33	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	0		
34	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	0		
35	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
36	11KV 50KVA transformer			No	0		
37	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	0		
		<b>KIBISH SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
38	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KIBISH SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	EXW Unit Price <sup>1</sup>	EXW Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>KOKURO 120kWp (120kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	120 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	120 kW (AC) Solar PV Inverters			Lot	1		
4	82 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	300 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	82 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation.			Lot	1		

		<b>KOKURO SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	137		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	137		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	7		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	91		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	96		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	26		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	60		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	7380		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	297.6		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	248		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	248		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	248		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	248		
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole (TSP/03/005-1)			No	23		
29	14M MV Concrete Pole (TSP/03/005-1)			No	4		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	27		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	1.82		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	13		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	3		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	3		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 50KVA transformer			No	2		
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	2		
<b>B5</b>	<b>Step up Transformer</b>						
37	415V/11KV 100KVA transformer			No	1		

38	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>KOKURO SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
39	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>KOKURO SUBTOTAL C</b>					

Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	EXW Unit Price <sup>1</sup>	EXW Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>OROPOI 100 kWp (100 kW AC) SOLAR PV MINI GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	100 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	100 kW (AC) Solar PV Inverters			Lot	1		
4	60 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	250 kWh Usable Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management system			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	60 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			No.	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			Lot	1		
12	Air conditioners for the control room as per specifications.			Lot	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Lot	1		

		<b>OROPOI SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	182		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	182		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	9		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	125		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	125		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	12		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	60		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	7350		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	296.4		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	247		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	247		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	247		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	247			
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1			
<b>B3</b>	<b>11KV MV Distribution line</b>							
28	11M MV Concrete Pole (TSP/03/005-1)			No	0			
29	12M MV Concrete Pole (TSP/03/005-1)			No	0			
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	0			
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line (TSP/06/020-2)			Km	0			
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	0			
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	0			
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0			
<b>B4</b>	<b>11KV Distribution Transformer</b>							
35	11KV 50KVA transformer			No	0			
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	0			
		<b>OROPOI SUBTOTAL B</b>						
<b>C</b>	<b>Mandatory spares</b>							
37	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1			
		<b>OROPOI SUBTOTAL C</b>						



Item	Description	Quantity and capacity of single unit <sup>2</sup>	Code <sup>3</sup>	Unit <sup>4</sup>	Qty	EXW Unit Price <sup>1</sup>	EXW Total Price <sup>1</sup>
					(1)	(2)	(1) x (2)
<b>NACHUKUI 120 kWp (120kW AC) SOLAR PV MINI-GRID</b>							
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>						
<b>A1</b>	<b>SPV Modules &amp; Inverters</b>						
1	120 kWp (DC) Standard monocrystalline silicon SPV modules			Lot	1		
2	Fixed-tilt racking structure(s) for above SPV modules including all necessary nuts and bolts as well as necessary clamps, foundation bolts etc.			Lot	1		
3	120 kW (AC) Solar PV Inverters			Lot	1		
4	82 kW Battery Inverter			Lot	1		
<b>A2</b>	<b>Battery Energy Storage System</b>						
5	300 kWh Battery Energy Storage System (BESS)			Lot	1		
6	Battery Management System			Lot	1		
7	Supply of SCADA along with associated equipment, data acquisition, data logger and display units and Industrial type PC with remote monitoring.			Lot	1		
<b>A3</b>	<b>Diesel Generator</b>						
8	82 kVA Prime Rated Diesel Generator(s) (DG) 415 V, 3-phase installed with a common genset controller capable of parallel operation with shunt-trip breakers for auto-start capability			Lot	1		
9	2000Litres Fuel Storage Tank			Lot	1		
<b>A4</b>	<b>Other SPGP Items</b>						
10	Metering system consisting of check and main meters for Import / export of energy from solar plant as per grid code			No.	1		
11	Auxiliary power supply as per specifications			No.	1		
12	Air conditioners for the control room as per specifications.			No.	1		
13	All balance of system components for interconnecting the battery and solar array with their inverters and the wider 415V three-phase 50 Hz AC distribution system, including but not limited to: AC & DC wiring, breakers, fuses, combiner boxes, recombiner boxes, panelboards, conduits, cables and cable trays, relays, transformers, enclosures, foundations, trenches, poles, support structures, cabinets, grounding electrodes, grounding conductors, lighting arrestors, lightning rods, insulators, surge protection, meters, sensors, and any other fixtures required for a safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation.			Lot	1		

		<b>NACHUKUI SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network (PDN)</b>						
<b>B1</b>	<b>3-phase and single-phase LV Distribution Line</b>						
14	10M LV Concrete Pole (TSP/03/005-1)			No	177		
15	LV Concrete Pole fittings- (Multipurpose/universal clamps, bolts,nuts,stays, prefomed guy-grips, D-irons, insulators, etc) (TSP/06/035), (TSP/03/021), (TSP/03/003), (TSP/02/004), (TSP/02/003- 1), (TSP/04/011), (TSP/02/003-2), (TSP/02/002), (TSP/06/036-1), (TSP/07/001), (TSP/03/022)			Set	177		
16	50sqmm AA bare conductor for length of LV (2-wire) line (TSP/06/020-2)			Km	13		
17	Complete Earthing- Protective Multiple Earthing (PME) (TSP/06/031-1)			No	158		
18	LV Concrete stays- (Stay wire, stay block, stay rod)			No	158		
19	LV Concrete strut pole- (Concrete strut pole, heavy duty clamps)			No	17		
<b>B2</b>	<b>Other PDN Items</b>						
20	Service Cable (25mm <sup>2</sup> PVC Insulated three phase, 4 core Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	30		
21	Service Cable (16mm <sup>2</sup> PVC Insulated Single Phase Concentric Aluminium Cable Without Two Core Copper Communication Cable) (TSP/05/004)			M	6360		
22	10mm dropper cable Red and Black; 1m each for single phase meters <sup>2</sup> (TSP/05/016)			M	255.6		
23	Service cable concrete fittings (TSP/02/004), (TSP/02/003-1), (TSP/04/011), (TSP/03/003), (TSP/06/035)			No.	213		
24	Service Cable fittings for wall mounting including Angle Iron (TSP/02/003-3), (TSP/04/011), (TSP/03/003), (TSP/02/003-1)			No.	213		
25	Ready Boards complete with mounting accessories (TSP/14/051)			No.	213		

26	1ftX1ftX3/4ft metallic meter boards (galvanized gauge 30 plain iron sheet) with wall mounting accessories and suitable for meter & MCB mounting, Service cable entry and Earthing			No	213		
27	Other Items not Mentioned above but required for installation and commissioning of the single and three phase Distribution line for Mini Grid and end user installation such as insulators, binding wires, fittings including nuts, bolts, Danger Plates, Name Plates, anti-climbing Barbed wire and accessories etc. on turn-key basis			Lot	1		
<b>B3</b>	<b>11KV MV Distribution line</b>						
28	12M MV Concrete Pole ( <a href="#">TSP/03/005-1</a> )			No	28		
29	14M MV Concrete Pole ( <a href="#">TSP/03/005-1</a> )			No	6		
30	MV Concrete Pole fittings- (Cross arms, Tie straps, insulator composites, Universal clamps, bolts, nuts, preformed guy-grips, D-irons, insulators, etc) ( <a href="#">TSP/06/035</a> ), ( <a href="#">TSP/03/021</a> ), ( <a href="#">TSP/03/003</a> ), ( <a href="#">TSP/02/004</a> ), ( <a href="#">TSP/02/003-1</a> ), ( <a href="#">TSP/04/011</a> ), ( <a href="#">TSP/02/003-2</a> ), ( <a href="#">TSP/02/002</a> ), ( <a href="#">TSP/06/036-1</a> ), ( <a href="#">TSP/07/001</a> ), ( <a href="#">TSP/03/022</a> )			Set	34		
31	75sqmm Aluminium Conductor Steel Reinforced (ACSR) conductor for length of three phase (3 - wire) line ( <a href="#">TSP/06/020-2</a> )			Km	1.88		
32	MV Concrete Pole stays - (Stay wire, stay rod, stay block, shackle insulator)			No	28		
33	MV Concrete Pole flying stays - (Concrete pole, Stay wire, stay rod, stay block, shackle insulator)			No	2		
34	MV Concrete Pole strut pole – (Concrete strut pole, heavy duty clamps)			No	0		
<b>B4</b>	<b>11KV Distribution Transformer</b>						
35	11KV 50KVA transformer			No	2		
36	11KV 50 - 200KVA transformer substation structure and fittings (Earthing & lightning Protection and associated material requirement, Expulsion Fuses, Surge diverters, Overhead fuse carriers, 10M Concrete poles, 11KV Steel channel and clamps etc. Danger plates, phase plates, circuit plates, number plates, anti-climbing devices and other safety requirements)			Set	2		
<b>B5</b>	<b>Step up Transformer</b>						
37	415V/11KV 100KVA transformer			No	1		

38	All system components for interconnecting the inverters and the 11kV distribution transformers, including but not limited to: panelboards, bus bars, switchgears, air break switch and structure, 11kv solid links, surge diverters, mounting structures for the surge diverters, underground cabling, conduits, cables and cable trays, grounding electrodes, grounding conductors, lightning arrestors, lightning mast galvanized steel structure and associated earthing, insulators, meters, sensors, concrete plinth, circuit breaker complete with its accessories, mounting structures for the HT neutral bushing and any other fixtures required for safety, reliability, and compliance with all relevant local and international codes and standards at the time of installation			Set	1		
		<b>NACHUKUI SUBTOTAL B</b>					
<b>C</b>	<b>Mandatory spares</b>						
39	Mandatory spares including at least 1 spare inverter, 5% of total solar PV panel capacity, fuses, cabling and hardware for 7 years including all consumable parts.			Lot	1		
		<b>NACHUKUI SUBTOTAL C</b>					
<b>TOTAL (to Schedule No. 7. Grand Summary)</b>							
		<b>Name of Bidder</b>		_____			
		<b>Signature of Bidder</b>		_____			
<sup>1</sup> Specify currency. Create and use as many columns for Unit Price and Total Price as there are currencies. <sup>2</sup> Bidder to provide further breakdown of items quoted for i.e. the exact number of single units that make up the item as well as the size/capacity of a single unit. <sup>3</sup> Lot per km - Bidders are advised to assume a span length of 100m for Medium Voltage network (11kV) and 50m for Low Voltage network. <b>NB – Refer to Employer’s Requirements &amp; Technical Specifications for details of each item (Bidding Documents Volumes II and IV)</b>							

**SCHEDULE NO. 3 - SURVEY & DESIGN SERVICES**

<b>LOT 1 SOLAR PV MINIGRIDS</b>					
Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
1	Survey and Design of SPV Modules & Inverters including structures	Lot	6		
2	Design of Battery Energy Storage System, including Inverter/Charger	Lot	6		
3	SCADA system design	Lot	6		
4	Diesel Generator Design	Lot	6		
5	Design of other SPGP items	Lot	6		
6	Survey and Design of Power Distribution Network	Lot	6		
7	Design of other PDN items	Lot	6		

8	Design of Civil/Structural works and associated works	Lot	6		
	<b>Lot 1 SUBTOTAL</b>				
<b>TOTAL (to Schedule No. 7. Grand Summary)</b>					
			<b>Name of Bidder</b>		
			<b>Signature of Bidder</b>		
<sup>1</sup> Specify currency in accordance with specifications in Bid Data Sheet under ITB 18.1					
<b>NB – Refer to Employer’s Requirements &amp; Technical Specifications for details of each item (Bidding Documents Volumes II and IV)</b>					
The design costs should include Survey (including picking distance of the solar plant from the existing KPLC grid), premises picking, customer sensitization, customer data collection, transformer positioning/picking, LV line wayleaves consent acquisition, and detailed design including design proposals/information updating on the KPLC Facility Data Base (FDB), preparation and submission of drawings. The civil and structural works design shall include Geotechnical Survey, Topographical Survey, hydrogeological survey and all Designs and drawings submission and all statutory approvals.					

**SCHEDULE NO. 4 - INSTALLATION, TESTING, COMMISSIONING AND OTHER SERVICES**

Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
<b>KAIKOR 175 kWp (175kW AC) SOLAR PV MINI GRID</b>					
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>				
1	Installation, Erection, Testing and Commissioning of SPV Modules & Inverters including Mounting structures	Lot	1		
2	Installation, Erection, Testing and Commissioning of Battery Energy Storage System, including Inverter/Charger	Lot	1		
3	Installation, Erection, Testing and Commissioning of SCADA system	Lot	1		
4	Installation, Erection, Testing and Commissioning of Diesel Generator				
5	Installation of all balance of system components to complete erection of the SPGP	Lot	1		
6	Testing & Commissioning of all supplied equipment including DG. Test running of Solar Power Plant as well as load trials at site, prior to handover and implementation of maintenance contract	Lot	1		
			<b>KAIKOR SUBTOTAL A</b>		
<b>B</b>	<b>Power Distribution Network</b>				
<b>B-1</b>	<b>Pegging, Erection, dressing and stringing of LV lines- 3 phase lines and Single phase lines</b>				
7	Pole Erection and dressing- Concrete	No	612		
8	Conductor Stringing including trace clearance as per KPLC standard	Km	35		
9	PME installation	No	431		
10	LV Stay hole digging, making & Erection	No	487		
11	LV Strut hole digging, making & Erection	No	34		
<b>B-2</b>	<b>Service cable</b>				
12	Service cable installation complete with terminations on both the pole and angle iron on the wall, pole mounted meter box, Prepaid meter and MCB installation	No.	561		
13	Installation of Ready Boards, Earthing and Testing	No.	561		
14	Installation of wall mounted metallic customer meter boards complete with MCB and service cable termination	No.	561		
15	Class C-2 ERC Wiring Certificates	No	561		
<b>B-3</b>	<b>Pegging, Erection, dressing and stringing of 11KV MV Distribution line</b>				
16	Pole Erection and dressing- Concrete	No	94		
17	Conductor Stringing including trace clearance as per KPLC standard	Km	4.83		
18	MV Stay hole digging, making & Erection	No	21		
19	MV Flying Stay hole digging, making & Erection	No	4		
20	MV Strut hole digging, making & Erection	No	7		

<b>B-4</b>	<b>Mounting, Dressing, Welding and Earthing 11KV Distribution Transformer</b>				
21	Transformer Mounting, Dressing, Welding and Earthing	No	4		
<b>B-5</b>	<b>Mounting, Dressing, Welding and Earthing Step up Transformer</b>				
22	Transformer Mounting, Dressing, Welding and Earthing	No	1		
<b>KAIKOR SUBTOTAL B</b>					
<b>C</b>	<b>Civil works</b>				
23	Platform Works-Earthworks and slope protection, site clearing and disposal, Galvanised Boundary chain link fence with steel posts for the entire minigrd developed area, Gates, SPGP area barricade fence. Solar panels reinforced concrete foundations/helical anchor foundations, Generator Equipment Plinth, 2000L underground fuel storage tank, Access road, SPGP Internal road, Storm water drainage.	Lot	1		
24	Cable network and conduits	Lot	1		
25	Containerized technology solution for Office Building and Control Room, Air conditioners.	Lot	1		
26	Galvanized Steel Structures- solar panels steel support structurers.	Lot	1		
27	Masonry guard house	Lot	1		
28	Masonry twin VIP Pit Latrine	Lot	1		
29	Security Systems, SPGP Outdoor Lighting and Perimeter Lighting, Control room and office building security lighting, Guard House Alarm System and danger and warning plate.	Lot	1		
30	Rain water harvesting and Storage	Lot	1		
31	Fire Prevention System-Fire Extinguishers, and Fire Suppression System at the BESS Section.	Lot	1		
<b>KAIKOR SUBTOTAL C</b>					

Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
<b>KANAKURDIO 75 kWp (75kW AC) SOLAR PV MINI GRID</b>					
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>				
1	Installation, Erection, Testing and Commissioning of SPV Modules & Inverters including Mounting structures	Lot	1		
2	Installation, Erection, Testing and Commissioning of Battery Energy Storage System, including Inverter/Charger	Lot	1		
3	Installation, Erection, Testing and Commissioning of SCADA system	Lot	1		
4	Installation, Erection, Testing and Commissioning Diesel Generator				
5	Installation of all balance of system components to complete erection of the SPGP	Lot	1		
6	Pre-commissioning & commissioning of all supplied equipment including DG. Test running of Solar Power Plant as well as load trials at site, prior to handover and implementation of maintenance contract	Lot	1		
<b>KANAKURDIO SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network</b>				
<b>B-1</b>	<b>Pegging, Erection, dressing and stringing of LV lines- 3 phase lines and Single phase lines</b>				
7	Pole Erection and dressing- Concrete	No	277		
8	Conductor Stringing including trace clearance as per KPLC standard	Km	16		
9	PME installation	No	187		
10	LV Stay hole digging, making & Erection	No	172		
11	LV Strut hole digging, making & Erection	No	34		
<b>B-2</b>	<b>Service cable</b>				
12	Service cable installation complete with terminations on both the pole and angle iron on the wall, pole mounted meter box, Prepaid meter and MCB installation	No.	226		
13	Installation of Ready Boards, Earthing and Testing	No.	226		
14	Installation of wall mounted metallic customer meter boards complete with MCB and service cable termination	No.	226		
15	Class C-2 ERC Wiring Certificates	No	226		
<b>B-3</b>	<b>Pegging, Erection, dressing and stringing of 11KV MV Distribution line</b>				
16	Pole Erection and dressing- Concrete	No	51		
17	Conductor Stringing including trace clearance as per KPLC standard	Km	4.28		
18	MV Stay hole digging, making & Erection	No	37		
19	MV Flying Stay hole digging, making & Erection	No	7		
20	MV Strut hole digging, making & Erection	No	0		



<b>B-4</b>	<b>Mounting, Dressing, Welding and Earthing 11KV Distribution Transformer</b>				
21	Transformer Mounting, Dressing, Welding and Earthing	No	2		
<b>B-5</b>	<b>Mounting, Dressing, Welding and Earthing Step up Transformer</b>				
22	Transformer Mounting, Dressing, Welding and Earthing	No	1		
	<b>Kanakurdio SUBTOTAL B</b>				
<b>C</b>	<b>Civil works</b>				
23	Platform Works-Earthworks and slope protection, site clearing and disposal, Galvanised Boundary chain link fence with steel posts for the entire minigrid developed area, Gates, SPGP area barricade fence. Solar panels reinforced concrete foundations/helical anchor foundations, Generator Equipment Plinth, 2000L underground fuel storage tank, Access road, SPGP Internal road, Storm water drainage.	Lot	1		
24	Cable network and conduits	Lot	1		
25	Containerized technology solution for Office Building and Control Room, Air conditioners.	Lot	1		
26	Galvanized Steel Structures- solar panels steel support structurers.	Lot	1		
27	Masonry guard house	Lot	1		
28	Masonry twin VIP Pit Latrine	Lot	1		
29	Security Systems, SPGP Outdoor Lighting and Perimeter Lighting, Control room and office building security lighting, Guard House Alarm System and danger and warning plate.	Lot	1		
30	Rain water harvesting and Storage	Lot	1		
31	Fire Prevention System-Fire Extinguishers, and Fire Suppression System at the BESS Section.	Lot	1		
	<b>KANAKURDIO SUBTOTAL C</b>				

Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
<b>KIBISH 120 kWp (120kW AC) SOLAR PV MINI GRID</b>					
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>				
1	Installation, Erection, Testing and Commissioning of SPV Modules & Inverters including Mounting structures	Lot	1		
2	Installation, Erection, Testing and Commissioning of Battery Energy Storage System, including Inverter/Charger	Lot	1		
3	Installation, Erection, Testing and Commissioning of SCADA system	Lot	1		
4	Installation, Erection, Testing and Commissioning Diesel Generator				
5	Installation of all balance of system components to complete erection of the SPGP	Lot	1		
6	Pre-commissioning & commissioning of all supplied equipment including DG. Test running of Solar Power Plant as well as load trials at site, prior to handover and implementation of maintenance contract	Lot	1		
			<b>KIBISH SUBTOTAL A</b>		
<b>B</b>	<b>Power Distribution Network</b>				
<b>B-1</b>	<b>Pegging, Erection, dressing and stringing of LV lines- 3 phase lines and Single phase lines</b>				
7	Pole Erection and dressing- Concrete	No	165		
8	Conductor Stringing including trace clearance as per KPLC standard	Km	9		
9	PME installation	No	105		
10	LV Stay hole digging, making & Erection	No	103		
11	LV Strut hole digging, making & Erection	No			
<b>B-2</b>	<b>Service cable</b>				
12	Service cable installation complete with terminations on both the pole and angle iron on the wall, pole mounted meter box, Prepaid meter and MCB installation	No.	225		
13	Installation of Ready Boards, Earthing and Testing	No.	225		
14	Installation of wall mounted metallic customer meter boards complete with MCB and service cable termination	No.	225		
15	Class C-2 ERC Wiring Certificates	No	225		
<b>B-3</b>	<b>Pegging, Erection, dressing and stringing of 11KV MV Distribution line</b>				
16	Pole Erection and dressing- Concrete	No	0		
17	Conductor Stringing including trace clearance as per KPLC standard	Km	0		
18	MV Stay hole digging, making & Erection	No	0		
19	MV Flying Stay hole digging, making & Erection	No	0		
20	MV Strut hole digging, making & Erection	No	0		

<b>B-4</b>	<b>Mounting, Dressing, Welding and Earthing 11KV Distribution Transformer</b>				
21	Transformer Mounting, Dressing, Welding and Earthing	No	0		
<b>KIBISH SUBTOTAL B</b>					
<b>C</b>	<b>Civil works</b>				
22	Platform Works-Earthworks and slope protection, site clearing and disposal, Galvanised Boundary chain link fence with steel posts for the entire minigrid developed area, Gates, SPGP area barricade fence. Solar panels reinforced concrete foundations/helical anchor foundations, Generator Equipment Plinth, 2000L underground fuel storage tank, Access road, SPGP Internal road, Storm water drainage.	Lot	1		
23	Cable network and conduits	Lot	1		
24	Containerized technology solution for Office Building and Control Room, Air conditioners.	Lot	1		
25	Galvanized Steel Structures- solar panels steel support structuriers.	Lot	1		
26	Masonry guard house	Lot	1		
27	Masonry twin VIP Pit Latrine	Lot	1		
28	Security Systems, SPGP Outdoor Lighting and Perimeter Lighting, Control room and office building security lighting, Guard House Alarm System and danger and warning plate.	Lot	1		
29	Rain water harvesting and Storage	Lot	1		
30	Fire Prevention System-Fire Extinguishers, and Fire Suppression System at the BESS Section.	Lot	1		
<b>KIBISH SUBTOTAL C</b>					

Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
<b>KOKURO 120 kWp (120kW AC) SOLAR PV MINI GRID</b>					
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>				
1	Installation, Erection, Testing and Commissioning of SPV Modules & Inverters including Mounting structures	Lot	1		
2	Installation, Erection, Testing and Commissioning of Battery Energy Storage System, including Inverter/Charger	Lot	1		
3	Installation, Erection, Testing and Commissioning of SCADA system	Lot	1		
4	Installation, Erection, Testing and Commissioning Diesel Generator				
5	Installation of all balance of system components to complete erection of the SPGP	Lot	1		
6	Pre-commissioning & commissioning of all supplied equipment including DG. Test running of Solar Power Plant as well as load trials at site, prior to handover and implementation of maintenance contract	Lot	1		
			<b>KOKURO SUBTOTAL A</b>		
<b>B</b>	<b>Power Distribution Network</b>				
<b>B-1</b>	<b>Pegging, Erection, dressing and stringing of LV lines- 3 phase lines and Single phase lines</b>				
7	Pole Erection and dressing- Concrete	No	137		
8	Conductor Stringing including trace clearance as per KPLC standard	Km	7		
9	PME installation	No	91		
10	LV Stay hole digging, making & Erection	No	96		
11	LV Strut hole digging, making & Erection	No	26		
<b>B-2</b>	<b>Service cable</b>				
12	Service cable installation complete with terminations on both the pole and angle iron on the wall, pole mounted meter box, Prepaid meter and MCB installation	No.	248		
13	Installation of Ready Boards, Earthing and Testing	No.	248		
14	Installation of wall mounted metallic customer meter boards complete with MCB and service cable termination	No.	248		
15	Class C-2 ERC Wiring Certificates	No	248		
<b>B-3</b>	<b>Pegging, Erection, dressing and stringing of 11KV MV Distribution line</b>				
16	Pole Erection and dressing- Concrete	No	27		
17	Conductor Stringing including trace clearance as per KPLC standard	Km	1.82		
18	MV Stay hole digging, making & Erection	No	13		
19	MV Flying Stay hole digging, making & Erection	No	3		
20	MV Strut hole digging, making & Erection	No	3		
<b>B-4</b>	<b>Mounting, Dressing, Welding and Earthing 11KV Distribution Transformer</b>				

21	Transformer Mounting, Dressing, Welding and Earthing	No	2		
<b>B-5</b>	<b>Mounting, Dressing, Welding and Earthing Step up Transformer</b>				
22	Transformer Mounting, Dressing, Welding and Earthing	No	1		
	<b>KOKURO SUBTOTAL B</b>				
<b>C</b>	<b>Civil works</b>				
23	Platform Works-Earthworks and slope protection, site clearing and disposal, Galvanised Boundary chain link fence with steel posts for the entire minigrid developed area, Gates, SPGP area barricade fence. Solar panels reinforced concrete foundations/helical anchor foundations, Generator Equipment Plinth, 2000L underground fuel storage tank, Access road, SPGP Internal road, Storm water drainage.	Lot	1		
24	Cable network and conduits	Lot	1		
25	Containerized technology solution for Office Building and Control Room, Air conditioners.	Lot	1		
26	Galvanized Steel Structures- solar panels steel support structurers.	Lot	1		
27	Masonry guard house	Lot	1		
28	Masonry twin VIP Pit Latrine	Lot	1		
29	Security Systems, SPGP Outdoor Lighting and Perimeter Lighting, Control room and office building security lighting, Guard House Alarm System and danger and warning plate.	Lot	1		
30	Rain water harvesting and Storage	Lot	1		
31	Fire Prevention System-Fire Extinguishers, and Fire Suppression System at the BESS Section.	Lot	1		
	<b>KOKURO SUBTOTAL C</b>				

Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
<b>OROPOI 100 kWp (100 kW AC) SOLAR PV MINI GRID</b>					
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>				
1	Installation, Erection, Testing and Commissioning of SPV Modules & Inverters including Mounting structures	Lot	1		
2	Installation, Erection, Testing and Commissioning of Battery Energy Storage System, including Inverter/Charger	Lot	1		
3	Installation, Erection, Testing and Commissioning of SCADA system	Lot	1		
4	Installation, Erection, Testing and Commissioning Diesel Generator				
5	Installation of all balance of system components to complete erection of the SPGP	Lot	1		
6	Pre-commissioning & commissioning of all supplied equipment including DG. Test running of Solar Power Plant as well as load trials at site, prior to handover and implementation of maintenance contract	Lot	1		
			<b>OROPOI SUBTOTAL A</b>		
<b>B</b>	<b>Power Distribution Network</b>				
<b>B-1</b>	<b>Pegging, Erection, dressing and stringing of LV lines- 3 phase lines and Single phase lines</b>				
7	Pole Erection and dressing- Concrete	No	182		
8	Conductor Stringing including trace clearance as per KPLC standard	Km	9		
9	PME installation	No	125		
10	LV Stay hole digging, making & Erection	No	125		
11	LV Strut hole digging, making & Erection	No	12		
<b>B-2</b>	<b>Service cable</b>				
12	Service cable installation complete with terminations on both the pole and angle iron on the wall, pole mounted meter box, Prepaid meter and MCB installation	No.	247		
13	Installation of Ready Boards, Earthing and Testing	No.	247		
14	Installation of wall mounted metallic customer meter boards complete with MCB and service cable termination	No.	247		
15	Class C-2 ERC Wiring Certificates	No	247		
<b>B-3</b>	<b>Pegging, Erection, dressing and stringing of 11KV MV Distribution line</b>				
16	Pole Erection and dressing- Concrete	No	0		
17	Conductor Stringing including trace clearance as per KPLC standard	Km	0		
18	MV Stay hole digging, making & Erection	No	0		
19	MV Flying Stay hole digging, making & Erection	No	0		
20	MV Strut hole digging, making & Erection	No	0		

<b>B-4</b>	<b>Mounting, Dressing, Welding and Earthing 11KV Distribution Transformer</b>				
21	Transformer Mounting, Dressing, Welding and Earthing	No	0		
<b>ORPOI SUBTOTAL B</b>					
<b>C</b>	<b>Civil works</b>				
22	Platform Works-Earthworks and slope protection, site clearing and disposal, Galvanised Boundary chain link fence with steel posts for the entire minigrid developed area, Gates, SPGP area barricade fence. Solar panels reinforced concrete foundations/helical anchor foundations, Generator Equipment Plinth, 2000L underground fuel storage tank, Access road, SPGP Internal road, Storm water drainage.	Lot	1		
23	Cable network and conduits	Lot	1		
24	Containerized technology solution for Office Building and Control Room, Air conditioners.	Lot	1		
25	Galvanized Steel Structures- solar panels steel support structuriers.	Lot	1		
26	Masonry guard house	Lot	1		
27	Masonry twin VIP Pit Latrine	Lot	1		
28	Security Systems, SPGP Outdoor Lighting and Perimeter Lighting, Control room and office building security lighting, Guard House Alarm System and danger and warning plate.	Lot	1		
29	Rain water harvesting and Storage	Lot	1		
30	Fire Prevention System-Fire Extinguishers, and Fire Suppression System at the BESS Section.	Lot	1		
<b>ORPOI SUBTOTAL C</b>					

Item	Description	Unit	Qty	Unit Price <sup>1</sup>	Total Price <sup>1</sup>
			(1)	(2)	(1) x (2)
<b>NACHUKUI 120 kWp (120kW AC) SOLAR PV MINI GRID</b>					
<b>A</b>	<b>Solar Power Generation Plant (SPGP)</b>				
1	Installation, Erection, Testing and Commissioning of SPV Modules & Inverters including Mounting structures	Lot	1		
2	Installation, Erection, Testing and Commissioning of Battery Energy Storage System, including Inverter/Charger	Lot	1		
3	Installation, Erection, Testing and Commissioning of SCADA system	Lot	1		
4	Installation, Erection, Testing and Commissioning Diesel Generator				
5	Installation of all balance of system components to complete erection of the SPGP	Lot	1		
6	Pre-commissioning & commissioning of all supplied equipment including DG. Test running of Solar Power Plant as well as load trials at site, prior to handover and implementation of maintenance contract	Lot	1		
<b>NACHUKUI SUBTOTAL A</b>					
<b>B</b>	<b>Power Distribution Network</b>				
<b>B-1</b>	<b>Pegging, Erection, dressing and stringing of LV lines- 3 phase lines and Single phase lines</b>				
7	Pole Erection and dressing- Concrete	No	177		
8	Conductor Stringing including trace clearance as per KPLC standard	Km	13		
9	PME installation	No	158		
10	LV Stay hole digging, making & Erection	No	158		
11	LV Strut hole digging, making & Erection	No	17		
<b>B-2</b>	<b>Service cable</b>				
12	Service cable installation complete with terminations on both the pole and angle iron on the wall, pole mounted meter box, Prepaid meter and MCB installation	No.	213		
13	Installation of Ready Boards, Earthing and Testing	No.	213		
14	Installation of wall mounted metallic customer meter boards complete with MCB and service cable termination	No.	213		
15	Class C-2 ERC Wiring Certificates	No			
<b>B-3</b>	<b>Pegging, Erection, dressing and stringing of 11KV MV Distribution line</b>				
16	Pole Erection and dressing- Concrete	No	34		
17	Conductor Stringing including trace clearance as per KPLC standard	Km	1.88		
18	MV Stay hole digging, making & Erection	No	28		
19	MV Flying Stay hole digging, making & Erection	No	2		
20	MV Strut hole digging, making & Erection	No	0		



<b>B-4</b>	<b>Mounting, Dressing, Welding and Earthing 11KV Distribution Transformer</b>				
21	Transformer Mounting, Dressing, Welding and Earthing	No	2		
<b>B-5</b>	<b>Mounting, Dressing, Welding and Earthing Step up Transformer</b>				
22	Transformer Mounting, Dressing, Welding and Earthing	No	1		
<b>NACHUKUI SUBTOTAL B</b>					
<b>C</b>	<b>Civil works</b>				
23	Platform Works-Earthworks and slope protection, site clearing and disposal, Galvanised Boundary chain link fence with steel posts for the entire minigrid developed area, Gates, SPGP area barricade fence. Solar panels reinforced concrete foundations/helical anchor foundations, Generator Equipment Plinth, 2000L underground fuel storage tank, Access road, SPGP Internal road, Storm water drainage.	Lot	1		
24	Cable network and conduits	Lot	1		
25	Containerized technology solution for Office Building and Control Room, Air conditioners.	Lot	1		
26	Galvanized Steel Structures- solar panels steel support structurers.	Lot	1		
27	Masonry guard house	Lot	1		
28	Masonry twin VIP Pit Latrine	Lot	1		
29	Security Systems, SPGP Outdoor Lighting and Perimeter Lighting, Control room and office building security lighting, Guard House Alarm System and danger and warning plate.	Lot	1		
30	Rain water harvesting and Storage	Lot	1		
31	Fire Prevention System-Fire Extinguishers, and Fire Suppression System at the BESS Section.	Lot	1		
<b>NACHUKUI SUBTOTAL C</b>					
<b>D</b>	<b>Others</b>				
32	Cost allocation for end-of-life (EOL) plan for all batteries and other potentially hazardous e-waste at the end of its useful life	Lot	1		
33	Offices facilities : Provide a furnished site office complete with communication facilities( Laptop, internet, printer and stationery)	Site	6		
34	Provision of communication facilities for the employer	Lot	1		
35	Provision of Transport: Provide fuel and maintain with driver transport for exclusive use of the REREC project engineer for project supervision and coordination services (1 No. 4X4)	Vehicle/ Months	12		
36	Factory Acceptance Tests for Major Items	Lumpsum	1		
37	Provisional sum for Community Project for compensation in kind for land acquisition (The project to be decided after land value is determined)	Fixed amount	6	KSh. 1,000,0 00	KSh. 6,000,000
<b>LOT 1 SUBTOTAL D</b>					
<b>TOTAL (To Schedule No. 7. Grand Summary)</b>					

Name of Bidder

Signature of Bidder

<sup>1</sup> Specify currency in accordance with ITB 18. Create and use as many columns for Unit Price and Total Price as there are currencies.

<sup>2</sup> Lot per km - Bidders are advised to assume a span length of 100m for Medium Voltage network (11kV) and 50m for Low Voltage network.

**SCHEDULE NO. 5 - ENVIRONMENTAL, SOCIAL, HEALTH AND SAFETY (ESHS) SERVICES**

Item	Description	Unit	Qty	Unit Price <sup>1</sup>		Total Price <sup>1</sup>	
			(Sites)	Foreign Currency Portion	Local Currency Portion	Foreign	Local
			(1)	(2)	(3)	(1) X (2)	(1) X (3)
<b>Air Quality: Dust and exhaust emissions</b>							
1	Sprinkle water to minimize dust generation	Lot	6				
2	Enclose/ cover/ water stockpiles of excavated soil during dry or windy conditions	Lot	6				
3	Conduct air quality measurements on a monthly basis	Lot	6				
<b>Solid Waste generation</b>							
4	Provide proper facilities for holding, separating and storing waste to reduce exposure and damage by elements of weather	Lot	6				
5	Contract NEMA registered waste handlers to dispose, hazardous, obsolete and E-waste and contaminated soil	Lot	6				
6	Store hazardous products and wastes separately in well labelled containers	Lot	6				
<b>Noise and Vibration</b>							
7	Conduct noise measurements on a monthly basis	Lot	6				
<b>Vegetation disturbance</b>							
8	Plant and nurture (200) indigenous trees in selected areas in public/community institutions	Lot	6				
<b>Fire hazards</b>							
9	Designate smoking zone, fire assembly point and provide appropriate firefighting equipment	Lot	6				
10	Provide trained fire marshals	Lot	6				
<b>Traffic congestion &amp; damage to roads and other existing infrastructure</b>							
11	Provide traffic marshals and signages	Lot	6				
<b>Occupational safety and Health risks</b>							
12	Awareness creation and training of staff on occupation health and safety issues	Lot	6				

13	Provide appropriate PPEs including Helmets, Safety Boots, Overalls, Dust Coats, Ear Muffs, Safety Harness, Gloves, Safety Glasses, etc	Lot	6				
14	Provide fully stocked first aid kit	Lot	6				
15	Provide insurance to the workers as per Work Injury and Benefits Act (WIBA) requirements	Lot	6				
16	Proper barricading and hazard communication and signage	Lot	6				
<b>Training and Sensitization on Labour influx related impacts (Gender based violence)-Sexual abuse and exploitation and sexual harassment, HIV/AIDs, Alcohol and drugs abuse and crime</b>							
17	Awareness creation to the workers and members of public on Abstinence, Being Faithful and Use of Condoms to prevent HIV/AIDs spread.	Lot	6				
18	Install information on the site billboard - 'Beware of HIV/AIDs, it's real, it kills' and other posters around site	Lot	6				
19	Provide adequate condoms at convenient locations	Lot	6				
<b>Risks related to spread of COVID-19 to workers and locals</b>							
20	Install hand washing facilities with adequate running water and soap	Lot	6				
21	Use thermal guns for everyone entering the site for monitoring temperatures levels	Lot	6				
<b>Stakeholder Engagement</b>							
22	Conduct stakeholder engagement forums in a culturally appropriate manner	Lot	6				
23	Conduct separate adequate public consultation for the VMGs where applicable	Lot	6				
<b>TOTAL (To Schedule No. 7. Grand Summary)</b>							
				Name of Bidder			
				Signature of Bidder			
<sup>1</sup> Specify currency in accordance with ITB 18. Create and use as many columns for Unit Price and Total Price as there are currencies. <b>NB – For details of each item, refer to the Environmental, Social, Health and Safety Management Plan for proposed solar mini-grid for community facilities, enterprises, and households - Component 1 of the Kenya Off-grid Solar Access Project (Bidding Document Volume I)</b>							

**SCHEDULE NO. 6 - OPERATION & MAINTENANCE**

Item	Description	Unit	Qty	% of O&M Contract Price	Unit Price <sup>1</sup>		Total Price <sup>1</sup>
					Local Currency Portion	Foreign Currency Portion	
						(optional)	
<b>KAIKOR 175 kWp (175kW AC) SOLAR PV MINI GRID</b>							
1	Operation and Maintenance of the Distribution Network and Plant Facility for FIRST YEAR	Year	1	11.5			
2	Operation and Maintenance of the Distribution Network and Plant Facility for SECOND YEAR	Year	1	11.5			
3	Operation and Maintenance of the Distribution Network and Plant Facility for THIRD YEAR	Year	1	11.5			
4	Operation and Maintenance of the Distribution Network and Plant Facility for FOURTH YEAR	Year	1	11.5			
5	Operation and Maintenance of the Distribution Network and Plant Facility for FIFTH YEAR	Year	1	18			
6	Operation and Maintenance of the Distribution Network and Plant Facility for SIXTH YEAR	Year	1	18			
7	Operation and Maintenance of the Distribution Network and Plant Facility for SEVENTH YEAR	Year	1	18			
<b>SUBTOTAL A</b>							
<b>KANAKURDIO 75 kWp (75kW AC) SOLAR PV MINI GRID</b>							
1	Operation and Maintenance of the Distribution Network and Plant Facility for FIRST YEAR	Year	1	11.5			
2	Operation and Maintenance of the Distribution Network and Plant Facility for SECOND YEAR	Year	1	11.5			
3	Operation and Maintenance of the Distribution Network and Plant Facility for THIRD YEAR	Year	1	11.5			
4	Operation and Maintenance of the Distribution Network and Plant Facility for FOURTH YEAR	Year	1	11.5			
5	Operation and Maintenance of the Distribution Network and Plant Facility for FIFTH YEAR	Year	1	18			
6	Operation and Maintenance of the Distribution Network and Plant Facility for SIXTH YEAR	Year	1	18			
7	Operation and Maintenance of the Distribution Network and Plant Facility for SEVENTH YEAR	Year	1	18			
<b>SUBTOTAL B</b>							

<b>KIBISH 120 kWp (120kW AC) SOLAR PV MINI GRID</b>							
1	Operation and Maintenance of the Distribution Network and Plant Facility for FIRST YEAR	Year	1	11.5			
2	Operation and Maintenance of the Distribution Network and Plant Facility for SECOND YEAR	Year	1	11.5			
3	Operation and Maintenance of the Distribution Network and Plant Facility for THIRD YEAR	Year	1	11.5			
4	Operation and Maintenance of the Distribution Network and Plant Facility for FOURTH YEAR	Year	1	11.5			
5	Operation and Maintenance of the Distribution Network and Plant Facility for FIFTH YEAR	Year	1	18			
6	Operation and Maintenance of the Distribution Network and Plant Facility for SIXTH YEAR	Year	1	18			
7	Operation and Maintenance of the Distribution Network and Plant Facility for SEVENTH YEAR	Year	1	18			
SUBTOTAL C							
<b>KOKURO 120 kWp (120kW AC) SOLAR PV MINI GRID</b>							
1	Operation and Maintenance of the Distribution Network and Plant Facility for FIRST YEAR	Year	1	11.5			
2	Operation and Maintenance of the Distribution Network and Plant Facility for SECOND YEAR	Year	1	11.5			
3	Operation and Maintenance of the Distribution Network and Plant Facility for THIRD YEAR	Year	1	11.5			
4	Operation and Maintenance of the Distribution Network and Plant Facility for FOURTH YEAR	Year	1	11.5			
5	Operation and Maintenance of the Distribution Network and Plant Facility for FIFTH YEAR	Year	1	18			
6	Operation and Maintenance of the Distribution Network and Plant Facility for SIXTH YEAR	Year	1	18			
7	Operation and Maintenance of the Distribution Network and Plant Facility for SEVENTH YEAR	Year	1	18			
SUBTOTAL D							
<b>OROPOI 100 kWp (100kW AC) SOLAR PV MINI GRID</b>							
1	Operation and Maintenance of the Distribution Network and Plant Facility for FIRST YEAR	Year	1	11.5			
2	Operation and Maintenance of the Distribution Network and Plant Facility for SECOND YEAR	Year	1	11.5			
3	Operation and Maintenance of the Distribution Network and Plant Facility for THIRD YEAR	Year	1	11.5			
4	Operation and Maintenance of the Distribution Network and Plant Facility for FOURTH YEAR	Year	1	11.5			
5	Operation and Maintenance of the Distribution Network and Plant Facility for FIFTH YEAR	Year	1	18			
6	Operation and Maintenance of the Distribution Network and Plant Facility for SIXTH YEAR	Year	1	18			

7	Operation and Maintenance of the Distribution Network and Plant Facility for SEVENTH YEAR	Year	1	18			
					SUBTOTAL E		

NACHUKUI 120 kWp (120kW AC) SOLAR PV MINI GRID							
1	Operation and Maintenance of the Distribution Network and Plant Facility for FIRST YEAR	Year	1	11.5			
2	Operation and Maintenance of the Distribution Network and Plant Facility for SECOND YEAR	Year	1	11.5			
3	Operation and Maintenance of the Distribution Network and Plant Facility for THIRD YEAR	Year	1	11.5			
4	Operation and Maintenance of the Distribution Network and Plant Facility for FOURTH YEAR	Year	1	11.5			
5	Operation and Maintenance of the Distribution Network and Plant Facility for FIFTH YEAR	Year	1	18			
6	Operation and Maintenance of the Distribution Network and Plant Facility for SIXTH YEAR	Year	1	18			
7	Operation and Maintenance of the Distribution Network and Plant Facility for SEVENTH YEAR	Year	1	18			
SUBTOTAL F							
<b>TOTAL (to Schedule No. 7. Grand Summary)</b>							
		<i>Name of Bidder</i>					
		<i>Signature of Bidder</i>					
<sup>1</sup> Specify currency in accordance with specifications in Bid Data Sheet under ITB 18.1							

**SCHEDULE NO. 7 - GRAND SUMMARY**

Item	Description	Total Price <sup>1</sup>	
		<i>Foreign</i>	<i>Local</i>
	<b>Phase 1 - Supply and Installation</b>		
1	Total Price of Schedule No 1 : Plant and Mandatory Spare Parts Supplied from Abroad		
2	Total Price of Schedule No 2 : Plant and Mandatory Spare Parts Supplied from Within the Employer's Country		
3	Total Price of Schedule No 3 : Survey & Design Services		
4	Total Price of Schedule No 4 : Installation, Testing, Commissioning, and Other Services		
5	Total Price of Schedule No 5 : Environmental, Social, Health And Safety (ESHS) Services		
	<b>Phase 2 - Operations and Maintenance</b>		
6	Total Price of Schedule No 6 : Operation & Maintenance		
	<b>TOTAL (to Letter of Bid)</b>		
		<i>Name of Bidder</i>	
		<i>Signature of Bidder</i>	



